



Vista Grande Watershed Study

Prepared by:
RMC
Water and Environment

August 2006

Acknowledgements

The Vista Grande Watershed Study has been prepared through a collaborative approach between the City of Daly City and the City and County of San Francisco. The following city departments participated in developing the Watershed Study:

City of Daly City Department of Public Works

City of Daly City Department of Water and Wastewater Resources

San Francisco Public Utilities Commission

San Francisco Department of Public Works

San Francisco Recreation and Park Department

In addition to RMC Water and Environment, the Vista Grande Watershed Study was developed by a consultant team that included:

Jacobs Associates – Conceptual design and technical review of the Vista Grande tunnel.

Alex Horne Associates – Conceptual design and technical review of the Vista Grande treatment wetlands.

Bartle Wells Associates – Development of local financing options for the Vista Grande Watershed Study.

Gus Yates, Consulting Hydrologist – Characterization of the groundwater hydrology of the project area.

Table of Contents

Executive Summary	ES-1
Chapter 1 Introduction.....	1-1
1.1 Intent of Document.....	1-1
1.2 Study Area and Watershed Description.....	1-1
1.2.1 Vista Grande Stormwater Collection System.....	1-3
1.2.2 Vista Grande Canal and Tunnel.....	1-4
1.2.3 Lake Merced.....	1-8
1.3 Hydrology.....	1-10
1.4 Problem Description.....	1-13
1.5 Organization of Document	1-13
Chapter 2 Project Approach and Objectives.....	2-1
2.1 Project Approach.....	2-1
2.1.1 Stakeholder Involvement	2-1
2.2 Study Goal and Objectives	2-2
Chapter 3 Previous Studies	3-1
3.1 Vista Grande Storm Sewer Project Draft Report (Kennedy/Jenks Engineers, 1983).....	3-1
3.2 Vista Grande Diversion Feasibility Evaluation, Lake Merced Technical Memorandum No.2 (CH2M Hill, 2001)	3-2
3.3 Vista Grande Stormwater Drainage Basin Hydraulic Capacity Evaluation (CH2M Hill, 2002).....	3-3
3.4 Initiative to Raise and Maintain Lake Level and Improve Water Quality (EDAW, September 2004a, b) – Task 3 and 4 Technical Memorandums.....	3-5
Chapter 4 Alternatives Considered	4-1
4.1 Upstream Alternatives	4-1
4.1.1 Storm Drain Improvements	4-1
4.1.2 Regional Detention Storage	4-2
4.1.3 Local Detention Storage.....	4-10
4.1.4 Best Management Practices (BMPs).....	4-12
4.2 Downstream Alternatives	4-12
4.2.1 Direct Discharge to Lake Merced.....	4-12
4.2.2 Detention Basin at Vista Grande Canal.....	4-13
4.2.3 Detention Basin at Impound Lake.....	4-15
4.2.4 Constructed Wetlands at Impound Lake	4-17
4.2.5 Structural Control Followed by Treatment Wetlands	4-19
4.2.6 Constructed Wetlands at Vista Grande Canal	4-20
4.2.7 New Parallel Tunnel.....	4-22
4.2.8 New Tunnel South of County Line.....	4-24
4.3 Alternatives Recommended for Further Evaluation	4-25
4.4 Interim Solutions	4-31
4.4.1 Diversion to Impound Lake	4-32
4.4.2 Diversion to South Lake	4-33
4.4.3 Bank Armoring	4-34
4.4.4 Recommendations Related to Interim Solutions.....	4-35
Chapter 5 Preliminary Program Recommendations	5-1
5.1 Summary of the Preliminary Program Recommendations	5-1

5.2	Tunnel South of County Line	5-3
5.2.1	<i>Description & Location</i>	5-3
5.2.2	<i>Objectives</i>	5-3
5.2.3	<i>Design Assumptions</i>	5-4
5.2.4	<i>Preliminary Layout and Facilities</i>	5-8
5.2.5	<i>Planning Level Cost Estimate</i>	5-17
5.2.6	<i>Operation and Maintenance</i>	5-20
5.2.7	<i>Benefits/Objectives Met</i>	5-21
5.2.8	<i>Implementation Issues</i>	5-21
5.2.9	<i>Implementation Schedule</i>	5-25
5.2.10	<i>Summary and Next Steps</i>	5-26
5.3	Vista Grande Wetland	5-29
5.3.1	<i>An Overview of Constructed Stormwater Wetlands</i>	5-29
5.3.2	<i>Vista Grande Wetland Project Description and Location</i>	5-29
5.3.3	<i>Objectives</i>	5-30
5.3.4	<i>Design Assumptions</i>	5-30
5.3.5	<i>Preliminary Layout</i>	5-30
5.3.6	<i>Water Quality Considerations and Treatment Characteristics</i>	5-36
5.3.7	<i>Wetland Construction, Operation and Maintenance</i>	5-43
5.3.8	<i>Preliminary Capital Costs</i>	5-45
5.3.9	<i>Benefits</i>	5-46
5.3.10	<i>Implementation Issues</i>	5-49
5.3.11	<i>Implementation Schedule</i>	5-53
5.3.12	<i>Recommendation and Next Steps</i>	5-53
5.4	Upstream Storm Drain Improvements.....	5-55
5.4.1	<i>Overview of Storm Drain Improvements</i>	5-55
5.4.2	<i>Existing System Description and System Constraints</i>	5-55
5.4.3	<i>Improvements to Address Storm Drain Capacity Issues</i>	5-55
5.4.4	<i>Runoff Reduction Practices</i>	5-58
5.4.5	<i>Storm Drain Master Planning</i>	5-58
5.4.6	<i>Preliminary Planning Level Cost Estimate</i>	5-59
5.4.7	<i>Planning and Implementation Schedule</i>	5-60
5.5	Ongoing Implementation of Best Management Practices	5-61
5.5.1	<i>Overview of Stormwater Regulation in Daly City</i>	5-61
5.5.2	<i>Regional NPDES Permit Coordination and Implementation</i>	5-61
5.5.3	<i>STOPPP Stormwater Management Plan</i>	5-61
5.5.4	<i>Daly City Ongoing Implementation of Performance Standards, BMPs, and other NPDES Permit Requirements</i>	5-63
5.5.5	<i>Recommendations for Ongoing BMP Implementation Related to Vista Grande Watershed Study</i>	5-67
Chapter 6 Implementation Strategies.....		6-1
6.1	Funding Strategies	6-1
6.1.1	<i>Local Financing Options</i>	6-1
6.1.2	<i>State and Federal Funding Opportunities</i>	6-2
6.2	Public Outreach and Community Involvement	6-6
6.3	Regulatory Requirements	6-7
6.3.1	<i>Local permits</i>	6-7
6.3.2	<i>State and Federal Permits</i>	6-7
6.3.3	<i>Environmental Documentation</i>	6-14
6.3.4	<i>Regulatory Summary and Recommendations</i>	6-15

6.4	Institutional Arrangements	6-18
6.5	Phasing and Schedule	6-18
6.5.1	<i>Program Phasing</i>	6-18
6.5.2	<i>Overall Implementation Schedule for the Vista Grande Watershed Study</i>	6-18
6.6	Next Steps.....	6-22

List of Tables

Table 1-1	Peak Flows at the Vista Grande Canal.....	1-11
Table 2-1	Primary and Secondary Objectives Developed for the Vista Grande Watershed Study	2-3
Table 3-1	Alternatives Analyzed in the Vista Grande Storm Sewer Report (Kennedy/Jenks, 1983.).....	3-2
Table 3-2	Alternatives Evaluated in the Vista Grande Diversion Feasibility Evaluation (CH2M Hill, 2002)	3-3
Table 3-3	Scenarios Analyzed in the Stormwater Drainage Basin Hydraulic Capacity Evaluation (CH2M Hill, 2002)	3-5
Table 4-1	Summary of Detention Basins Studied in the Vista Grande Hydraulic Capacity Evaluation (CH2M Hill, 2002)	4-4
Table 4-2	Planning Level Cost Estimate for I-280 Cloverleaf Detention Basin	4-5
Table 4-3	Planning Level Cost Estimate for LMGC Detention Basins	4-7
Table 4-4	Planning Level Capital Cost Estimate for Westlake Shopping Center Detention Basin	4-8
Table 4-5	Planning Level Cost Estimate for Park Plaza Drive Detention Basins.....	4-10
Table 4-6	Planning Level Cost Estimate for Vista Grande Detention Basin	4-15
Table 4-7	Planning Level Cost Estimate for Detention Basin at Impound Lake	4-16
Table 4-8	Impound Lake Planning Level Cost Estimate.....	4-19
Table 4-9	Structural Control Followed By Treatment Wetlands Planning Level Cost Estimate	4-20
Table 4-10	Vista Grande Wetland Cost Estimate	4-21
Table 4-11	New Parallel Tunnel Cost Estimate	4-23
Table 4-12	Tunnel South of County Line Cost Estimate	4-25
Table 4-13	Comparison of Long-Term Program Improvements	4-27
Table 5-1	Overall Planning Level Cost Estimate for the Vista Grande Watershed Preliminary Program.....	5-2
Table 5-2	Hydraulic Design Criteria.....	5-5
Table 5-3	Estimated Costs for Tunnel South of County Line Alternative 1 – John Muir Drive Site	5-18
Table 5-4	Estimated Costs for Tunnel South of County Line Alternative 2 – Doelger Community Center Site	5-19
Table 5-5	Estimated Costs for Tunnel South of County Line Alternative 3 – John Daly Alignment	5-20
Table 5-6	Summary of Permit Requirements for the Tunnel South of County Line	5-23
Table 5-7	Alternative Summary and Comparison.....	5-26
Table 5-8	Baseline Average Concentrations of Critical Constituents.....	5-37
Table 5-9	N:P Ratios for South Lake.....	5-38
Table 5-10	Pollutants Removal for Different Stormwater Inflow Rates at the Vista Grande Wetland.....	5-40

Table 5-11	Pollutants Removal for Different Recycled Water Inflow Rates at the Vista Grande Wetland	5-42
Table 5-12	Maximum Recommended Wetland Treatment Rates for Stormwater and Recycled Water	5-43
Table 5-13	Vista Grande Wetland Alternative A Planning Level Capital Cost Estimate	5-46
Table 5-14	Scenarios for Providing Supplemental Water to Lake Merced and Effect on Lake Water Level.....	5-48
Table 5-15	Summary of Permit Requirements for the Vista Grande Wetland.....	5-50
Table 5-16	Possible Combinations of Water Supplies for Operation of the Vista Grande Wetland.....	5-54
Table 5-17	Daly City Stormwater Implementation Team.....	5-64
Table 5-18	Summary of Daly City’s Ongoing Implementation of Stormwater BMP, Activities, and Actions Related to the STOPPP SMP for Fiscal Year 2004/2005	5-65
Table 5-19	Projects Affected by C.3 Provisions for the San Mateo Countywide NPDES permit.....	5-67
Table 6-1	Potential Funding Sources	6-3
Table 6-2	State and Federal Legislators	6-5
Table 6-3	Summary of State and Federal Regulatory Requirements	6-16
Table 6-4	Summary of Recommended Institutional Arrangements.....	6-18

List of Figures

Figure 1-1	Location of Vista Grande Drainage Basin	1-2
Figure 1-2	Vista Grande Watershed	1-3
Figure 1-3	Vista Grande Watershed Flooding Locations	1-4
Figure 1-4	Upstream End of Vista Grande Canal.....	1-5
Figure 1-5	Access Road to Vista Grande Canal	1-5
Figure 1-6	Vista Grande Canal Narrow Section.....	1-6
Figure 1-7	Vista Grande Tunnel Entrance.....	1-6
Figure 1-8	Vista Grande Canal/Tunnel Interface	1-7
Figure 1-9	Vista Grande Outfall Located on the Beach below Fort Funston – Facing North	1-7
Figure 1-10	South Lake	1-8
Figure 1-11	Trail between South Lake and Impound Lake	1-9
Figure 1-12	Vista Grande Canal Overflow at John Muir Boulevard.....	1-10
Figure 1-13	Vista Grande Watershed Water Balance.....	1-11
Figure 1-14	Upstream Flooding in the Vista Grande Watershed	1-12
Figure 1-15	Sheet flow from Vista Grande Canal Overflows	1-12
Figure 3-1	Simulated Lake Level and Water Addition Rates: Seasonal Additions, Multiple-Year Average Hydrologic Conditions	3-7
Figure 3-2	Supplemental Water Requirements for Alternative Lake Levels: Seasonal Additions, Multiple-Year Average Hydrologic Conditions.....	3-7
Figure 4-1	Location of detention basins modeled in the Vista Grande Hydraulic Capacity Evaluation (CH2M Hill, 2002)	4-3
Figure 4-2	Example of underground reservoir construction.....	4-4
Figure 4-3	I-280 Detention Basin Location.....	4-5
Figure 4-4	Location of LMGC Detention Basins	4-6
Figure 4-5	Location of Westlake Shopping Center Detention Basin	4-8
Figure 4-6	Park Plaza Drive Detention Basins	4-9
Figure 4-7	Example of CULTEC Chambers (source: CULTEC, Inc., 2005).....	4-11

Figure 4-8	Use of park for detention of storm flows (Source: Clark County Regional Flood Control District, Las Vegas, NV.)	4-11
Figure 4-9	Location of Vista Grande Detention Basin	4-14
Figure 4-10	Conceptual Cross Sectional View of Vista Grande Detention Basin	4-14
Figure 4-11	Schematic of Detention Basin at Impound Lake	4-16
Figure 4-12	Schematic of Impound Lake Wetlands	4-18
Figure 4-13	Schematic of Constructed Wetlands at Vista Grande Canal	4-21
Figure 4-14	New Parallel Tunnel	4-23
Figure 4-15	New Tunnel South of County Line	4-24
Figure 4-16	Long-Term Program Components Recommended for Further Evaluation in the Vista Grande Watershed Study	4-31
Figure 4-17	Location of Interim Solutions Examined for the Vista Grande Watershed Study	4-32
Figure 4-18	Schematic of Impound Lake Diversion Interim Solution	4-32
Figure 4-19	Schematic of South Lake Interim Solution	4-33
Figure 5-1	Long-Term Program Components Recommended for Further Evaluation in the Vista Grande Watershed Study	5-1
Figure 5-2	Tunnel South of County Line Alternative Map	5-3
Figure 5-3	Serra Fault Location.....	5-5
Figure 5-4	Typical tunnel boring machine	5-6
Figure 5-5	Typical construction layout.....	5-6
Figure 5-6	Typical tunnel portal.....	5-6
Figure 5-7	Typical construction shaft.....	5-7
Figure 5-8	Alternative 1 Tunnel Profile	5-9
Figure 5-9	John Muir Drive Site.....	5-10
Figure 5-10	Fort Funston Beach Outlet Location.....	5-11
Figure 5-11	San Francisco CSO Structure.....	5-11
Figure 5-12	Alternative 2 Tunnel Profile	5-12
Figure 5-13	Doelger Community Center Site.....	5-13
Figure 5-14	John Daly Alignment Primary Construction Site	5-14
Figure 5-15	Alternative 3 Tunnel Profile	5-15
Figure 5-16	John Daly Alignment Retrieval Location Construction Site	5-16
Figure 5-17	Thornton State Beach Outlet Location	5-17
Figure 5-18	Alternative 1 Implementation Schedule.....	5-26
Figure 5-19	Typical Processes Occurring in a Treatment Wetland.....	5-29
Figure 5-20	Cattail and Bulrush	5-31
Figure 5-21	Vista Grande Wetland Site Map	5-32
Figure 5-22	Vista Grande Wetland Layout	5-33
Figure 5-23	Vista Grande Wetland Profile.....	5-34
Figure 5-24	Vista Grande Wetland Cross-Sections.....	5-35
Figure 5-25	Area Along Existing Canal Proposed for Construction of Vista Grande Wetland	5-44
Figure 5-26	Impound Lake Fringe Habitat.....	5-49
Figure 5-27	Property Ownership around the Vista Grande Canal.....	5-52
Figure 5-28	Vista Grande Wetland Implementation Schedule.....	5-53
Figure 5-29	Localized Flooding near Daly City's City Hall	5-56
Figure 5-30	Implementation Schedule for Storm Drain Improvements a	5-60
Figure 5-31	Gateway Gardens.....	5-63
Figure 6-1	Regulatory Jurisdiction of the U.S. Army Corps of Engineers (CERES, 2002).....	6-8
Figure 6-2	Regulatory Agency Relationships.....	6-17
Figure 6-3	General Schedule for the Watershed Study	6-19
Figure 6-4	Overall Implementation Schedule.....	6-21

Appendices

Appendix A - Vista Grande Watershed Peak Stormwater Discharge for Various Design Storms

Appendix B - July 2005 Stakeholder Workshop Attendance List

Appendix C - Upstream Detention Storage Alternative Supporting Technical Information

Appendix D - Evaluation of Interim Solutions

Appendix E - Tunnel South of County Line Supporting Technical Information

Appendix F - Cost Estimate and Schematics for Vista Grande Wetland Alternative B

Appendix G - Cost Estimate Escalation Information

Appendix H - March 2006 Stakeholder Workshop Attendance List

List of Abbreviations

ac-ft/yr	acre-feet per year
AF	acre-feet
Basin Plan	San Francisco Bay Basin Plan
BASMAA	Bay Area Stormwater Management Agencies Association
BCDC	Bay Conservation and Development Commission
BMPs	Best Management Practices
BOD	Biochemical Oxygen Demand
C/CAG	City/County Association of Governments
California State Parks	California Department of Parks and Recreation
Caltrans	California Department of Transportation
CARCD	California Association of Resource Conservation Districts
CCC	California Coastal Commission
CCSF	City and County of San Francisco
CDFG	California Department of Fish and Game
CDS	Continuous Deflection System
CEQA.	California Environmental Quality Act
CERES	California Environmental Resources Evaluation System
cfs	cubic feet per second
CNPS	California Native Plant Society
COPs	Certificates of Participation
Corps	US Army Corps of Engineers
CSO	San Francisco Combined Sewer Overflow
CY	Cubic yards
Daly City	City of Daly City
DWWR	Daly City Department of Water and Wastewater Resources
EA	Environmental Assessment
EIR	Environmental Impact Report
EIS	Environmental Impact Statement
EPA	US Environmental Protection Agency
FONSI	Finding of No Significant Impact
ft	feet
GGNRA	Golden Gate National Recreation Area
GO	General Obligation
gpd	gallons per day
gpm	gallons per minute
I-280	Interstate-280
JARPA	San Francisco Joint Aquatic Resource Permit Application
JPA	Joint Powers Authority
Kennedy/Jenks	Kennedy/Jenks Engineers
kg	kilogram
kg/day	kilogram per day
LCP	Local Coastal Program
LMGC	Lake Merced Golf Club
MG	million gallons
mg/L	milligram per liter
mgd	million gallons per day
mL	milliliter
MOU	Memorandum of Understanding
MPN	Most Probable Number
NEPA	National Environmental Policy Act
NMFS	National Marine Fisheries Service
NOAA	National Oceanic and Atmospheric Administration

List of Abbreviations

NPDES	National Pollution Discharge Elimination System
NPS	National Park Service
NSMCSD	North San Mateo County Sanitation District
O&M	Operation and Maintenance
Prop 40	Proposition 40
Prop 50	Proposition 50
RWQCB	Regional Water Quality Control Board
SF city datum	San Francisco city datum
SFE	San Francisco Estuary
SFPUC	San Francisco Public Utilities Commission
SFRPD	San Francisco Recreation and Park Department
SMP	Stormwater Management Plan
STOPPP	San Mateo Countywide Stormwater Pollution Prevention Program
SWMM	Stormwater Management Model
SWRCB	State Water Resources Control Board
TAC	NPDES Technical Advisory Committee
TBM	Tunnel Boring Machine
TMDLs	Total Maximum Daily Loads
TMs	Technical Memoranda
TSS	Total Suspended Solids
USFWS	US Fish and Wildlife Service
WAM	Watershed and Monitoring
WDRs	Waste Discharge Requirements
WRDA	Water Resources Development Act
WWTP	Waste Water Treatment Plant